

Door Schedule (#)				
Mark	rk Qty Size Description			
1	6	3'-0" x 6'-8"	Colonist Textured Molded Composite Interior Door	
2	2	2'-8" x 6'-8"	Colonist Textured Molded Composite Interior Door	
3	9	2'-0 x 6'-8"	Colonist Textured Molded Composite Interior Door	
4	2	1'-4" x 6'-8"	Colonist Textured Molded Composite Interior Door	
5	1	3'-0" x 6'-8"	Flat Panel Single Lite Exterior Door	
6	1	3'-0" x 6'-8"	Colonist Flat Exterior Door	
7	1	3'-0" x 6'-8"	Aluminum Full Glass Storm Dorr	

Window Schedule #					
Mark	k Qty Size Description		Description		
1	18	2'-8" x 5'-1"	4 Pane Single Hung Wood Windows		
2	2	2'-8" x 2'-7"	Colonist Textured Molded Composite Interior Door		

AREAS			
SQ. FT.	AREA (Gross Area)		
2027	Main Office Building		
225	Enclosed Carport		
2252	TOTAL AREA		

## PROPOSED RENOVATION PLAN

(TO BE FINALIZED DURING PERMITTING)

Upon approval of Specific Use Permit final drawings will be submitted for building permit with the based on the final changes:

1	Remove enclosed Carport. Remove concrete pad and replace with Landscaping.		
2	Combine Office 4 and Office 5 to create Boardroom		
3	Relocate Hot Water Tank (Replace with Tankless) and HVAC Unit in closet to Utility Room		
4	Remove all walls between Kitchen and Team Collaboration Space (Adding required Structural Support)		
5	Redesign Kitchen layout		
6	Remove all existing finishes to studs and replace with new Insulation, Drywall, Flooring and Trim		
7	Replace Pluming and Electrical fixtures		
8	Refinish Exterior - Paint Exterior Brick and Vertical Siding and TrimRepair Existing exterior brick caused to settlement.		
9	Replace Exterior Doors and Windows.		
10	Clean up front and back landscaping and ground cover.		

Date: 9/23/2023		
Drawn by: Danny Eldridge	Current Property Owner: Kara Elizabeth Jones Trust	
Version: 1.0	Specific Use Permit Change from OTK Neighborhood Subdistrict to	
	OTK Neighborhood Subdistrict SUP for office	

Renovation 147 S Elm Street, Keller, Texas
BEN Investment LLC

Existing	Floor F	Plan and	Schedu	les
•				