

Duplicate Copy

To :

ENTERPRISE FLEET SERVICES
1420 WEST MOCKINGBIRD LANE #640
DALLAS TEXAS 75247
United States

Quotation Valid Thru : 08/08/2019

Terms : NET 10 DAYS

Attention : JENNIFER BERTRAM

We are pleased to quote your requirements as shown below. Our company has a reputation for delivering quality products on time and we look forward to the opportunity of serving you.

Prices do not include any Federal, State, or Local taxes unless otherwise indicated.

Item	Facility / Part / Rev / Description / Details	Quantity Quoted	Unit Price	Extended Price
001	Default INSTALL Rev NS U/M EA INSTALL ON DUAL REAR WHEELS FORD F650 108 CLEAN CA 9FT RAWSON KOENIG MODEL S60DW94, MED DUTY CHASSIS BODY 3 20" DEEP COMPARTMENTS PER/SIDE, 44" HIGH INSTALL CUSTOMER SUPPLIED DOOSAN UNIT TWO HOSE REELS (1) 100' 1/2" HOSE WITH MOUNTED IN FRONT RIGHT COMPARTMENT ABOVE TOOL BOX AIR / WATER FILTER (2) 50' 3/4" HOSE WITH MOUNTED IN FRONT RIGHT COMPARTMENT ABOVE TOOL BOX AIR/ WATER FILTER HOSE REELS ARE HANNAY REELS PART #618-30-31-15.5A CUSTOM BUILD TRAY FOR BRASS FITTINGS ON STREET SIDE HORIZONTAL COMPARTMENT OVER WHEEL WELL. (SEE PICS) DRAWER UNIT IN FRONT CURBSIDE COMPARTMENT (DRAWINGS TO FOLLOW) PULL OUT (2) SHELF DRAWER CURBSIDE HORIZONTAL OVER WHEEL COMPARTMENT (DRAWINGS TO FOLLOW) TREADPLATE LINER ON COMPARTMENT TOPS ONLY CUT WHEEL WELLS FOR 22.5 TIRES TREADPLATE LINER ON COMPARTMENT TOPS ONLY	1.0000	36,342.0000	US\$ 36,342.00

To :

ENTERPRISE FLEET SERVICES
1420 WEST MOCKINGBIRD LANE #640
DALLAS TEXAS 75247
United States

Quotation Valid Thru : 08/08/2019

Attention : JENNIFER BERTRAM

Item	Facility / Part / Rev / Description / Details	Quantity Quoted	Unit Price	Extended Price
	20" BUMPER W/ CABLE STEPS (SEE PICS) INSTALL CUSTOMER SUPPLIED JACKHAMMER HOLDER CURBSIDE (SEE PICS) INSTALL CUSTOMER SUPPLIED VICE / MOUNT CURBSIDE STAINLESS STEEL 3-POINT T HANDLE LATCHES STANDARD SHELVING AND DIVIDERS, 54" WIDE FLOOR 1/2" STEEL TREADPLATE REINFORCED PINTLE BUMPER W/ 50 TON PINTLE (BP760A) PLATFORM MOUNTED ON FRAME RAILS BETWEEN TRUCK CAB 48"X 92" AND SERVICE BODY. INSTALL CUSTOMER SUPPLIED SULLAIR UNIT FABRICATE EXPANDED METAL SHOVEL RACK BETWEEN SULLAIR UNIT AND BULKHEAD OF SERVICE BODY (SEE PICTURES) FABRICATE EXPANDED METAL BASKET UNDER PLATFORM STREET SIDE AND CURBSIDE (SEE PICTURES) LIGHTS AND REFLECTORS, PLAIN MUD FLAPS FACTORY PAINT OUTSIDE WHITE TO MATCH CAB SPRAY LINE CARGO, TAILGATE, BUMPER AREA OF SERVICE BODY			



Our Quotation # 037262-00

08/08/2018

To :

ENTERPRISE FLEET SERVICES
1420 WEST MOCKINGBIRD LANE #640
DALLAS TEXAS 75247
United States

Quotation Valid Thru : 08/08/2019

Attention : JENNIFER BERTRAM

Item	Facility / Part / Rev / Description / Details	Quantity Quoted	Unit Price	Extended Price
	3500 WATT POWER BRIGHT INVERTER WITH GFI PLUG AT REAR OF BODY ON PASSENGER SIDE FABRICATE LADDER RACK / PIPE RACK ON STREETSIDE OF BODY(SEE PICS) TWO WATER JUG HOLDERS (SEE PICS) TWO HAND PULLS ON REAR OF TRUCK (SEE PICS) TAIL LIGHTS TO BE MOUNTED TOP EDGE OF SERVICE BODY (AGAIN SEE PICS) CUSTOM BUILD HEADACHE RACK (SEE PICTURES) NOTE: THIS ORDER IS FOR ONLY THOSE LISTED ITEMS AND DOES NOT INCLUDE ANY OTHER ITEMS.			

Orders cancelled for any reason will be subject to 100% of all labor cost incurred up to the time of cancellation, 25% restocking fee of all standard parts, 100% of all special order parts having to be returned to the vendor (including freight) or parts deemed as not able to be used on additional jobs, and 75% of selling price of all fabricated parts.

Thanks again for your interest in our company as one of your suppliers.

Prices do not include any Federal, State, or Local taxes unless otherwise indicated.