FLEMISH BOND COURSING BAND

EXTERIOR FINISH SCHEDULE

ITEM	COLOR	MANUFACTURER	REMARKS
F-1 BRICK VENEER	ALMOND	INTERSTATE BRICK	GROUT SPEC COLOR – SPEC MIX, SM750 SILVERSTONE COURSING – RUNNING BOND
F-2 BRICK VENEER	ALMOND	INTERSTATE BRICK	GROUT SPEC COLOR – SPEC MIX, SM750 SILVERSTONE COURSING – FLEMISH BOND
F-3 BRICK VENEER	ALMOND	INTERSTATE BRICK	GROUT SPEC COLOR – SPEC MIX, SM750 SILVERSTONE COURSING – ROWLOCK
P-1 PAINT FINISH	MATCH BRICK COLOR, F-1	SHERWIN WILLIAMS	FIELD COLOR
M-1 PREFINISHED METAL COPING	MED BRONZE	BEST SOURCE	–
M-2 PRE-ENGINEERED METAL CANOPY	MED BRONZE	ARCHITECTURAL FABRICATION	FACTORY APPLIED FINISH
STOREFRONT FRAMES	DARK BRONZE ANODIZED	KAWNEER	REFER TO WINDOW AND DOOR SCHEDULE
DOWN SPOUTS	MATCH COLOR, P-1	LOCAL SOURCE	PREFINISHED
EIFS	–	PAREX OR EQUAL	SANDBLAST FINISH

**COLORS AND MANUFACTURERS INDICATED ARE PREFERRED. G.C. SHALL SUBMIT SAMPLES OF PROPOSED ALTERNATES FOR ARCHITECT'S APPROVAL
BRICK TO BE ORDERED FROM BLACKSON BRICK (NO SUBSTITUTIONS) CONTACT: BRAE BARTON 817.874.3194 BRAE@BLACKSONBRICK.COM

FINISH LEGEND

BRICK EIFS

1 WEST ELEVATION
SCALE: 3/16" = 1'-0"

WEST ELEVATION		
BRICK	1,056 SF	58%
EIFS	767 SF	42%
TOTAL AREA	1,823 SF	100%

ROWLOCK COURSING AT SF WINDOWS

2 NORTH ELEVATION
SCALE: 3/16" = 1'-0"

NORTH ELEVATION		
BRICK	435 SF	15%
EIFS	2,458 SF	85%
TOTAL AREA	2,893 SF	100%

PRELIMINARY
NOT TO BE USED FOR REGULATORY APPROVAL, PERMITTING OR CONSTRUCTION

FRANZ architects
7608 Bentbrook Parkway
Bentbrook, Texas 76126
(817) 737-0922
www.Franzarchitects.com

SHELL BUILDING
FM 1709 KELLER-SMITHFIELD ROAD
KELLER, TX

Revisions:

File Name: 24182– A2.1a
Project No: 24182
Date: 01/10/25
Drawn By: JLB
Checked By: TI

SHEET
A2.1a
EXTERIOR ELEVATIONS

COPYRIGHT © 2025