



SOW/QUOTE

info@kmisportsconstruction.com
512-287-9636

BILL TO

KYA Baseball
200 Sports Pkwy
Keller, TX 76248
Attn: Greg Silvestri
817-832-8896
gssilvestri@verizon.net

Remit to Address:
KMI Sports
Construction LLC
PO BOX 829
Dripping Springs, TX
78620

SOW#18-4231v2	
Quote Date	7/18/18
Customer	Greg

DATE	YOUR ORDER #	OUR ORDER #	SALES REP.	F.O.B.	SHIP VIA	TERMS	TAX ID
7/18/18			SK				

QTY	ITEM	UNITS	DESCRIPTION	TAXABLE	NOTES	TOTAL
1	KYAB		See page 2 for the details regarding this Statement of Work	N/A		

Terms: Down payment is due up front. Remaining balance is due at the time of project completion.

Visit us at: www.KMISportsConstruction.com

Subtotal	\$103,789.30
Deposit/Down	\$83,789.30
Due at Completion	\$20,000.00
Miscellaneous	
TOTAL	\$103,789.30

Batting Cage Section 1 - 64' x 74'	
Item	Qty
Concrete Curb	276' around x 4" deep concrete curb (64'x74' area)
3/8"-1/2" Gravel	Fill and compact the 64'x74' area with gravel material
Poles	16 - 3"x16' galvanied poles
2 3/8" Poles	16 - 2 3/8" x 10' galv poles
Chainlink/Toprails	300' of 8' galv chainlink + top rails
5' Gate	5' x 8' galv gate
Cages	4 - 15'W x 12'H x 70'L cages
Cabling	550' of cables
Cable Fitting	clampes, carrabiners, turn buckles
Turf	4736 sq ft of Turf over compacted gravel
Total	35952.96

Batting Cage Section 2 - 34' x 74'	
Item	Qty
Concrete Curb	216' around x 4" deep concrete curb (34'x74' area)
3/8"-1/2" Gravel	Fill and compact the 34'x74' area with gravel material
Poles	12 - 3"x16' galvanied poles
2 3/8" Poles	12 - 2 3/8" x 10' galv poles
Chainlink/Toprails	216' of 8' galv chainlink + top rails
Gate	5' x 8' galv gate
Cages	2 - 15'W x 12'H x 70'L cages
Cabling	315' of cable
Cable Fitting	clampes, carrabiners, turn buckles
Turf	2516 sq ft of Turf over compacted gravel
Total	21482.84

Batting Cage Section 3 - 34' x 74'	
Item	Qty
Concrete Curb	216' around x 4" deep concrete curb (34'x74' area)
3/8"-1/2" Gravel	Fill and compact the 34'x74' area with gravel material
Poles	12 - 3"x15" galvanied poles
2 3/8" Poles	12 - 2 3/8" x 10' galv poles
Chainlink/Toprails	216' of 8' galv chainlink + top rails
Gate	5' x 8' galv gate
Cages	2 - 15'W x 12'H x 70'L cages
Cabling	315' of cables
Cable Fitting	clampes, carrabiners, turn buckles
Turf	2516 sq ft of Turf over compacted gravel
Total	21482.84

Pitching Section - 64' x 70'	
Item	Qty
Concrete Curb	268' around x 4" deep concrete curb (64'x70' area)
3/8"-1/2" Gravel	Fill and compact the 64'x70' area with gravel material
Turf	4480 sq ft of Turf over compacted gravel
Poles	4 - 3"x15' galvanized poles
Cabling	75' of cables
Net	64'x12' netting
Total	24870.68