

812 E. 9th Street Fort Worth, TX 76102 Phone: 817.870.2266 Fax: 817.870.2268 www.fortworthelec.com

BID PROPOSAL Job Name: Keller Municipal Bld. 200 kw Generator Date: 02/15/2022 To: City of Keller Bid Number: 4616 C Attn: William Richards Job Location: Keller, Texas

***This bid is in compliance with the TRWD Blanket Contract, purchase order ID 21-140 that expires 11/15/22 M/WBE, SBE & HUB Certified HFMB50818Y1012

Scope of Work:

- FWE shall furnish, wire, and install (1) new 200kw 3-phase 120/208 Cummins Generator (Please see attached specifications below)
- FWE shall furnish, wire, and install (1) new Cummins transfer switch
- FWE shall route new conduit and wire from the main distribution panel to the new transfer switch.
- FWE shall route new conduit and wire from the new transfer switch to the new generator.
- FWE shall intercept the primary feed to the build and route to a new main service disconnect.
- FWE shall route new conduit and wire from the new transfer switch and refeed the main building distribution panel.
- FWE shall make all final electrical connections to the generator, transfer switch, and main distribution panel.
- FWE shall furnish, wire, and install (1) new 300-amp panel to replace and upgrade the existing 100-amp generator panel in the main distribution room.
- FWE shall transfer the existing generator backed up circuits to the new electrical panel.
- FWE shall disconnect and remove the existing 40kw transfer switch and existing generator feed.
- FWE shall provide new concrete pad for generator to be placed on.

- FWE shall set the new generator on the new concrete pad.
- FWE shall provide concrete cut and pour back for conduit installation for the new generator.
- FWE shall run and load test the new generator.
- Diesel fuel to be provided by others.
- Work shall be performed during regular business hours.

Alternate #1:

FWE shall disconnect, remove, and purchase the existing 40kw Caterpillar generator. Please deduct (**Five Thousand Dollars** --- **\$5,000.00**) from the base bid.

Bid Includes:

Labor / Materials / Electrical Panel / Breakers / 200kw Generator / Transfer Switch / Remote Generator Monitoring / Saw Cut / Concrete Patch / Rental Equipment / Concrete Generator Pad / Engineer Sealed Drawings

Bid Excludes:

Night Work / Weekend Work / Diesel Fuel / Utility Work / Tax

All of the above work, except alternates as shown, to be completed, Due upon completion for the sum of:

Two Hundred Twenty Six Thousand Four Hundred Thirty Five Dollars and XX Cents -- \$237,756.00

All Work will be performed as required by National and local electrical codes, with payment to be made as follow: Progress payments for material stored and work completed including change orders, are due upon receipt of invoice. Additional work and/or changes will be executed upon written order, and will become an extra charge over and above the prices specified. In the event payment is not made on completion of work as agreed, a 1.5% finance charge will be assessed on all overdue invoices and immediate action will be taken to collect. Any and all expenses incurred to do so, including attorney fees, will be paid by the customer. This bid is contingent upon the full execution of acceptable contract documents. This proposal may be withdrawn by us if not accepted by March 31, 2022.

Justin Aaron		02/15/2022
Submitted By:	-	Date